

04-10-03

PTO/SB/21 (03-03)

Approved for use through 04/30/2003. OMB 0651-0031
U.S. Patent and Trademark Office: U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

3643

**TRANSMITTAL
FORM**

(to be used for all correspondence after initial filing)

TRANSMITTAL FORM (to be used for all correspondence after initial filing)	Application Number	10/006,017	
	Filing Date	December 4, 2001	
	First Named Inventor	Burns, John G.	
	Group Art Unit	3643	
	Examiner Name	Unknown	
Total Number of Items in This Submission	6	Attorney Docket Number	717901.19

ENCLOSURES (check all that apply)

<input type="checkbox"/> Fee Transmittal Form <input type="checkbox"/> Fee Attached <input type="checkbox"/> Amendment / Reply <input type="checkbox"/> After Final <input type="checkbox"/> Affidavits/declaration(s) <input type="checkbox"/> Extension of Time Request <input type="checkbox"/> Express Abandonment Request <input type="checkbox"/> Information Disclosure Statement <input checked="" type="checkbox"/> Certified Copy of Priority Document(s) <input type="checkbox"/> Response to Missing Parts/ Incomplete Application <input type="checkbox"/> Response to Missing Parts under 37 CFR 1.52 or 1.53	<input type="checkbox"/> Drawing(s) <input type="checkbox"/> Licensing-related Papers <input type="checkbox"/> Petition <input type="checkbox"/> Petition to Convert to a Provisional Application <input type="checkbox"/> Power of Attorney, Revocation Change of Correspondence Address <input type="checkbox"/> Terminal Disclaimer <input type="checkbox"/> Request for Refund <input type="checkbox"/> CD, Number of CD(s) _____	<input type="checkbox"/> After Allowance Communication to a Technology Center (TC) <input type="checkbox"/> Appeal Communication to Board of Appeals and Interferences <input type="checkbox"/> Appeal Communication to TC (Appeal Notice, Brief, Reply Brief) <input type="checkbox"/> Proprietary Information <input type="checkbox"/> Status Letter <input checked="" type="checkbox"/> Other Enclosure(s) (please identify below) Priority Claim; return postcard.
Remarks:		

SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT

Firm or Individual Name	Kevin M. Kercher, Reg. No. 33,408 Blackwell Sanders Peper Martin LLP
Signature	<i>[Signature]</i>
Date	Apr. 19, 2003

RECEIVED

APR 16 2003

GROUP 3600**CERTIFICATE OF TRANSMISSION/EXPRESS MAILING**

I hereby certify that this correspondence is being facsimile transmitted to the USPTO or deposited with the United States Postal Service with sufficient postage as Express Mail in an envelope addressed to: Commissioner for Patents, Washington, DC 20231 on this date: April 9, 2003. Express Mail Label No.: EV202549215US			
Typed or printed name	Beth Hookway		
Signature	<i>Beth Hookway</i>	Date	4-9-03

This collection of information is required by 37 CFR 1.5. This information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you are required to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

If you need assistance in completing the form, call 1-800-PTO-9199 (1-800-786-9199) and select option 2.



PATENT 717901.19

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re Application of: John Granville Burns)
)
U. S. Patent Application Serial Number: 10/006,017)
)
U.S. Filing Date: December 4, 2001)
)
PCT No.: PCT/GB00/02134)
)
International Filing Date: June 2, 2000)
)
Priority Data: June 4, 1999)
(U.K. Patent No. 9912909.0))
)
Priority Data: May 30, 2000)
(U.K. Patent No. 0012882.7))
)
For: PLAYING SURFACE SUBSTRATE, IN)
PARTICULAR TURF MATS)
)
Publication No. US 2002/0045489 A1)
Attorney Docket: 717901.19)

Examiner: Unknown.

Group Art Unit: 3643

Confirmation No. 7708

Customer No. 27128

10
Priority
Paper
Cover
5-17-04

RECEIVED

APR 16 2003

GROUP 3600

**PREVIOUSLY MADE PRIORITY CLAIM UNDER 35 U.S.C. § 119 BY THE FILING OF
CERTIFIED COPIES OF PRIORITY PATENT APPLICATIONS**


Applicant is hereby submitting certified copies of PCT Application No.
PCT/GB00/02134 that was filed 2 June 2000, Great Britain Patent Application No. 9912909.0
that was filed 4 June 1999 and Great Britain Patent Application No. 0012882.7 that was filed 30
May 2000. This perfects the previously made claim to priority.

If you have any questions or comments, please do not hesitate to contact the undersigned
attorney listed below.

Respectfully submitted,

Date:

April 9, 2003



Kevin M. Kercher

Reg. No. 33,408

Blackwell Sanders Peper Martin LLP

720 Olive Street, 24th Floor

St. Louis, Missouri 63101

(314) 345-6000

ATTORNEY(S) FOR APPLICANT

**WORLD INTELLECTUAL PROPERTY
ORGANIZATION**

世界知识产权组织

**ORGANIZACION MUNDIAL
DE LA PROPIEDAD INTELECTUAL**



**ORGANISATION MONDIALE
DE LA PROPRIÉTÉ INTELLECTUELLE**

المنظمة العالمية للملكية الفكرية

**ВСЕМИРНАЯ ОРГАНИЗАЦИЯ
ИНТЕЛЛЕКТУАЛЬНОЙ СОБСТВЕННОСТИ**



RECEIVED

APR 16 2003

GROUP 3600

CERTIFICATION

It is hereby certified that the attached copy is a true copy of the record copy of International Application No. PCT/GB00/02134, filed with the United Kingdom Patent Office as receiving Office on 02 June 2000 (02.06.00) and received by the International Bureau on 28 June 2000 (28.06.00), including any pages containing corrections and/or rectifications transmitted by the competent Authority to, and received by, the International Bureau before the completion of the technical preparations for international publication.

By: The International Bureau



Linda Schwaab
Head
PCT Examination Section II

Date: 21 January 2003 (21.01.03)

Record.

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

* Title changed. See IJR.

For receiving Office use only

International Application No. PCT/GB 0 0 / 0 2 1 3 4

International Filing Date (02-06-00) = 2 JUNE 2000

United Kingdom Patent Office
PCT International Application

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum)

Box No. I TITLE OF INVENTION

PLAYING SURFACE SUBSTRATE *

RECEIVED

APR 16 2003

Box No. II APPLICANT

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

BURNS JOHN GRANVILLE. [M.]
THE OLD SCHOOL.
FORGHEN
TURKIFF
SCOTLAND AB53 4JJ GB

☒ This person is also inventor.

Telephone No.

01888 562618.

Facsimile No.

N/A.

Teleprinter No.

N/A.

State (that is, country) of nationality:

UNITED KINGDOM. [B.K.]

State (that is, country) of residence:

[SCOTLAND] UNITED KINGDOM

This person is applicant for the purposes of:

☒ all designated States☐ all designated States except the United States of America☐ the United States of America only☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

N/A.

This person is:

☐ applicant only☐ applicant and inventor☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:

State (that is, country) of residence:

This person is applicant for the purposes of:

☐ all designated States☐ all designated States except the United States of America☐ the United States of America only☐ the States indicated in the Supplemental Box☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:

☐ agent☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

N/A.

Telephone No.

Facsimile No.

Teleprinter No.

☐ Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Box No.V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☒ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☒ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ **EP European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☒ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)


National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input checked="" type="checkbox"/> AE United Arab Emirates | <input checked="" type="checkbox"/> LR Liberia |
| <input checked="" type="checkbox"/> AL Albania | <input checked="" type="checkbox"/> LS Lesotho |
| <input checked="" type="checkbox"/> AM Armenia | <input checked="" type="checkbox"/> LT Lithuania |
| <input checked="" type="checkbox"/> AT Austria | <input checked="" type="checkbox"/> LU Luxembourg |
| <input checked="" type="checkbox"/> AU Australia | <input checked="" type="checkbox"/> LV Latvia |
| <input checked="" type="checkbox"/> AZ Azerbaijan | <input checked="" type="checkbox"/> MD Republic of Moldova |
| <input checked="" type="checkbox"/> BA Bosnia and Herzegovina | <input checked="" type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> BB Barbados | <input checked="" type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input checked="" type="checkbox"/> BG Bulgaria | <input checked="" type="checkbox"/> MN Mongolia |
| <input checked="" type="checkbox"/> BR Brazil | <input checked="" type="checkbox"/> MW Malawi |
| <input checked="" type="checkbox"/> BY Belarus | <input checked="" type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> CA Canada | <input checked="" type="checkbox"/> NO Norway |
| <input checked="" type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input checked="" type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CN China | <input checked="" type="checkbox"/> PL Poland |
| <input checked="" type="checkbox"/> CU Cuba | <input checked="" type="checkbox"/> PT Portugal |
| <input checked="" type="checkbox"/> CZ Czech Republic | <input checked="" type="checkbox"/> RO Romania |
| <input checked="" type="checkbox"/> DE Germany | <input checked="" type="checkbox"/> RU Russian Federation |
| <input checked="" type="checkbox"/> DK Denmark | <input checked="" type="checkbox"/> SD Sudan |
| <input checked="" type="checkbox"/> EE Estonia | <input checked="" type="checkbox"/> SE Sweden |
| <input checked="" type="checkbox"/> ES Spain | <input checked="" type="checkbox"/> SG Singapore |
| <input checked="" type="checkbox"/> FI Finland | <input checked="" type="checkbox"/> SI Slovenia |
| <input checked="" type="checkbox"/> GB United Kingdom | <input checked="" type="checkbox"/> SK Slovakia |
| <input checked="" type="checkbox"/> GD Grenada | <input checked="" type="checkbox"/> SL Sierra Leone |
| <input checked="" type="checkbox"/> GE Georgia | <input checked="" type="checkbox"/> TJ Tajikistan |
| <input checked="" type="checkbox"/> GH Ghana | <input checked="" type="checkbox"/> TM Turkmenistan |
| <input checked="" type="checkbox"/> GM Gambia | <input checked="" type="checkbox"/> TR Turkey |
| <input checked="" type="checkbox"/> HR Croatia | <input checked="" type="checkbox"/> TT Trinidad and Tobago |
| <input checked="" type="checkbox"/> HU Hungary | <input checked="" type="checkbox"/> UA Ukraine |
| <input checked="" type="checkbox"/> ID Indonesia | <input checked="" type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> IL Israel | <input checked="" type="checkbox"/> US United States of America |
| <input checked="" type="checkbox"/> IN India | <input checked="" type="checkbox"/> UZ Uzbekistan |
| <input checked="" type="checkbox"/> IS Iceland | <input checked="" type="checkbox"/> VN Viet Nam |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> KE Kenya | <input checked="" type="checkbox"/> ZA South Africa |
| <input checked="" type="checkbox"/> KG Kyrgyzstan | <input checked="" type="checkbox"/> ZW Zimbabwe |
| <input checked="" type="checkbox"/> KP Democratic People's Republic of Korea | |
| <input checked="" type="checkbox"/> KR Republic of Korea | |
| <input checked="" type="checkbox"/> KZ Kazakhstan | |
| <input checked="" type="checkbox"/> LC Saint Lucia | |
| <input checked="" type="checkbox"/> LK Sri Lanka | |

Check-boxes reserved for designating States which have become party to the PCT after issuance of this sheet:

- ☒ **ALGERIA** **DZ**
- ☒ **MOZAMBIQUE** **MZ**
- ☒ **ANTIGUA AND BARBUDA** **AG**

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM		<input checked="" type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application: regional Office	international application: receiving Office
item (1) (04.06.99) 4 JUNE 1999	9912909.0	U.K. GB	NEWPORT	
item (2) [SEE COVERING LETTER]				
item (3) (30-05-00) 30 MAY 2000	0012882.7	GB		
<input type="checkbox"/> The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s):				
<i>* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which that earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.</i>				
Box No. VII INTERNATIONAL SEARCHING AUTHORITY				
Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):		Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):		
ISA /		Date (day/month/year)	Number	Country (or regional Office)
Box No. VIII CHECK LIST; LANGUAGE OF FILING				
This international application contains the following number of sheets:		This international application is accompanied by the item(s) marked below:		
request : 3		1. <input checked="" type="checkbox"/> fee calculation sheet		
description (excluding sequence listing part) : 30		2. <input type="checkbox"/> separate signed power of attorney		
claims : 2		3. <input type="checkbox"/> copy of general power of attorney; reference number, if any:		
abstract : 1		4. <input type="checkbox"/> statement explaining lack of signature		
drawings : 3		5. <input checked="" type="checkbox"/> priority document(s) identified in Box No. VI as item(s):		
sequence listing part of description :		6. <input type="checkbox"/> translation of international application into (language):		
Total number of sheets : 37		7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material		
		8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form		
		9. <input checked="" type="checkbox"/> other (specify): COVERING LETTER.		
Figure of the drawings which should accompany the abstract:		Language of filing of the international application:		
Box No. IX SIGNATURE OF APPLICANT OR AGENT				
Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).				
 30. MAY. 2000.				

For receiving Office use only		For International Bureau use only	
1. Date of actual receipt of the purported international application: - 2 JUNE 2000 (02-06-00)	2. Drawings: <input checked="" type="checkbox"/> received: <input type="checkbox"/> not received:		
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:			
4. Date of timely receipt of the required corrections under PCT Article 11(2):			
5. International Searching Authority (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid.		

For International Bureau use only	
Date of receipt of the record copy by the International Bureau: 28 JUNE 2000 (28.06.00)	

Playing Surface Substrate

The present invention relates to a substrate material for use as a playing surface. In particular, the substrate material 5 is for use as a playing surface substrate for practising and/or playing golf.

To facilitate learning or practising the game of golf it is common to use the facilities provided at a golf driving range. 10 Golf driving ranges generally provide practice areas provided with practice mats. Typically, the practice mats are rectangular in shape and are formed arranged to provide a player standing area and at least one or more pre-set locations for placement of golf tees.

15

The practice mats are generally placed on the floor of the driving range, which is typically made from concrete or some other similar substance which is hard and non-resilient. In addition to the foregoing there are also commercially 20 available relatively expensive practice mats. These mats are generally provided on raised support platforms which are formed from a rigid plastic material or wood.

It has been found that repeated playing off on practice areas 25 of the abovementioned types can lead to various repetitive

stress injuries similar to tennis elbow. These injuries are generally caused by the inadvertent striking of the more or less hard non-resilient playing surface of the practice mat/block with the golf-club. The resulting jarring effect is transmitted to the joints (particularly the elbow and shoulder joints) of the player. Repeated jarring of this type has been found to result in injury to the connective tissue in and/or around the affected joints.

10 Practice mats/platforms of this type allow the player to practice and/or learn only a limited range of strokes. Only those strokes which require the golf ball to be resting on a tee or those strokes which do not require the club to strike the underside of the golf ball (for example, when putting back spin onto a golf ball) can be practised. Playing strokes of the type which require the club to strike the underside of the golf ball greatly increases the possibility of the club striking the practice mat, and so increase the likelihood of injury to the player.

20

It is also a particular feature of these practice mats that there is only a limited number of pre-selected locations for placement of tees. This limitation of the restricted number and locations for placement of tees does not suit all of the

many individual playing styles or the different statures of individuals wishing to use the practice mats/platforms.

It is an object of the present invention to avoid or minimise one or more of the foregoing disadvantages.

The present invention is directed towards the provision of a mat suitable for use as a playing surface which is flexible, resilient and can deform more or less like natural turf or grass under the impact of a golf club. The mat is also robust enough to be walked upon without sustaining damage to the mat.

In a first aspect of the present invention, there is provided a mat suitable for use as a playing surface and comprises a honeycomb form support matrix packed with a filler material.

The support matrix may be in the form of a more or less integrally-formed structure or conveniently is in the form of a close packed assembly of substantially upright tubes packed with filler material.

20

The tubes are generally formed from a reasonably flexible and deformable material to facilitate close packing thereof and enable the mat to yield under the impact of for example, a golf club. Suitable materials that may be mentioned include one or more of: plastics film or sheeting which is preferably

biodegradable, paper, cardboard, and textile sheet materials of natural or synthetic fibres which may be woven or non-woven. Furthermore, the material used to fabricate the tubes may be porous or non-porous. It would be particularly desirable to choose a material which is porous to facilitate the movement of moisture (or excess water) into and out of the tubes thereby avoiding for example water-logging of the mat in wet conditions or in the case of over-watering.

10 The tubes are preferably generally cylindrical in shape, however they may be square, rectangle, elliptical or polygonal in section. Typically, the tubes are packed in a hexagonal close packed configuration. Alternatively the tubes are arranged in a less closely packed arrangement such as a square
15 close packed configuration. It will also be appreciated that with tubes of a generally flexible material, the tubes may be deformed to a greater or lesser extent resulting in even closer packing together.

20 Typically, the tubes have a diameter of from 0.5 cm to 10 cm, preferably from 1 cm to 5 cm and most preferably from 1 cm to 3 cm. The tubes typically have a height of from 3 cm to 25 cm, preferably from 5 cm to 15 cm and most preferably from 5 cm to 10 cm. It will of course be realised that these
25 dimensions can be altered and varied according to particular

requirements. Furthermore, it is also envisaged that tubes of different diameters may be present within the mat. In this case the arrangement of the tubes may be regular as above or it may be more random to accommodate the different sizes of 5 tubes more efficiently. The tubes may also be closed at the bottom end portion to provide a tube which is open only at the top portion.

Adjacent tubes in the mat may be bonded or otherwise attached 10 together at one or more shared edges or sides of said adjacent tubes. Preferably the tubes are glued together along the mutually co-operating edges or sides. The bonding of the tubes together has the beneficial effect of providing additional strength and robustness to the mat. Furthermore, 15 bonding the tubes together allows easier handling and placement in use of the mat.

The filler material is generally packed into the tubes sufficiently tightly so that the filler material resists 20 falling out of the tubes when the mat is being manoeuvred or otherwise handled. On the other hand, it is normally desirable to avoid excessively tight packing that could result in compaction of the filler and loss of resilience in the playing surface. Suitable packing conditions may be readily 25 determined by simple trial and error.

Once packed with filler material, the tubes may optionally be sealed to provide a tube which is closed at the top and/or bottom portions. It is particularly desirable to seal the 5 tubes where a material is used which is more prone to falling out of the tubes when the mat is being manoeuvred or otherwise handled. Filler materials with little or no interlocking capacity such as sand, grit, polymer beads or chips and the like are examples of such filler materials.

10

The integrally-formed or close packed assembly structure of the mat allows easy handling by being in the form of a continuous layer of support matrix.

15 The mat of the present invention generally provides a playing surface more representative of natural turf and grass surfaces found on golf courses than the currently available golf practice mats/platforms. The mat has more naturally deformable properties due to the use of the filler material, 20 in addition to reasonable structural stability, in use, (to lateral and vertically applied forces) when a golf club strikes the mat, when a player stands on the mat, and/or for the placement of golf tees.

Furthermore, in use, when a player strikes the mat with a golf club, the mat deforms under the impact of the club in a manner very similar to natural turf or grass surfaces, with a reduced possibility of injury to the player over that of the prior art
5 practice mats/platforms. The abovementioned advantageous properties of the mat allow a player to play a wider range of strokes than is possible with currently available practice mats/platforms.

10 The filler material can be chosen to mimic the properties of a particular golf course or any other desired playing surface. To achieve this, the filler material conveniently comprises at least one of, the following materials: soil such as various types of loam, sphagnum moss, peat, wood chips/shavings,
15 sawdust, clay, sand, polymer chips/beads/fragments, and papier mache. Where a filler material is for example very fibrous it will have a large number of interconnected and/or interwoven fibres which provide a stabilising network within which it is possible to incorporate further non-fibrous or fibrous filler
20 materials. The choice of filler material providing the stabilising network of fibres, may be varied to adjust or modify the density of interconnected and/or interwoven fibres to provide a range of different stabilising effects. For example, where a further filler material such as sand (which
25 has little or no interlocking properties) is used, it may be

necessary to use a filler material with a relatively high content and density of interconnected and/or interwoven fibres to prevent the sand from settling at the bottom of the support matrix, in order to maintain a uniform distribution of sand 5 and fibrous filler material throughout the support matrix.

Where substantially non-absorbent and/or non-water swellable filler material is used e.g. sand, certain polymer chips/beads (it will be appreciated that some types of polymer chips/beads 10 will be water absorbent and/or water swellable), it would generally be desirable also to include one or more other filler materials which are water absorbent and/or expandable (e.g. woodchips, sawdust, sphagnum moss), depending upon the desired playing properties required of the mat.

15

It will be appreciated that materials such as loam are available with a wide variety of properties and textures and for example may be peaty, fibrous or non-fibrous or clay-like. The abovementioned filler materials are not intended to be 20 exhaustive, but merely illustrative of the types of filler material which may be used in accordance with the present invention.

The filler material (within the mat) may be used in either a 25 wet or dry condition. It would generally be more convenient

to have the filler material in the dry state for transportation of the mats in order to minimise carriage costs and facilitate handling of the mats. Once installed, the filler material can have water added thereto if so desired.

5 Where it is desirable for the filler material in the mat to be in a wet/damp condition prior to installation it is desirable to use a support matrix which is resistant to the effects (such as rotting and tearing) of long term exposure to damp or humid conditions. The filler material and/or the material
10 from which the material are fabricated, can also be admixed or treated with one or more additives to prevent mould or fungus (or other similar conditions) growing thereon through exposure to water or damp conditions.

15 It will be appreciated that the packing material will generally have a certain moisture content sufficient to prevent excessive or unwanted settlement thereof when in a non-use condition. This moisture content will of course vary from material to material, and can readily be determined by
20 simple experimentation.

The filler material within the tubes is preferably dry when the mat is being stored in a non-use condition. In this way the mat is relatively light and easy to manoeuvre. Before
25 use, water can be added to the filler material. The water

generally causes the material to swell and/or become heavier and therefore becomes more tightly bound within the tubes and any supporting frame or container. The amount of water added to the mat in addition to the composition of the particular
5 playing surface filler material can be varied to suit whichever playing surface condition(s) is desired to be mimicked, thereby increasing the variety and number of conditions available to play or practice on.

10 Preferably or alternatively, there may be used a binder material (in combination of the abovementioned filler materials) which contains one or more additives which are capable of forming a semi-interpenetrating network (semi-IPN) or interpenetrating network (IPN) within the tube. The binder
15 material can be used to bind together one or more filler materials that have little or no interlocking ability as described previously herein.

The use of a binder material allows the use of materials which
20 would not normally be considered for use as such due to the lack of sufficient interlockability and/or being too dense and/or not being dense enough.

Binder materials are generally those which are not solvents
25 for the filler material, and may be formed from one or a

mixture of polymerisable monomers and/or polymers. Suitable monomers and/or polymers are preferably those capable of forming polyolefins and may be thermoplastic or thermosetting. When polyfunctional monomers and/or polymers are used, then a continuous cross-linked polymer system can be formed from the monomer and/or polymer. A semi-IPN is obtained when one of the co-continuous systems (i.e. the pre-existing polymer) is cross-linked. When both systems (i.e. the pre-existing polymer and the polymerised monomer) are cross-linked, an IPN is formed. The formation of a semi-IPN/IPN within the tube also provides additional structural stability to the mat as a whole, in addition to helping to retain other filler materials in the tube.

The additive which forms the semi-IPN/IPN may be one, or a mixture or more than one, type of monomer which is polymerisable to form said semi-IPN/IPN. The polymerisation of the monomer(s) is preferably effected within the tubes prior to use of the mat. The polymerisation is preferably ionic, most preferably cationic.

Desirably urea and formaldehyde are co-monomers, which are polymerised to form a co-polymer. The urea and formaldehyde are co-polymerised by the addition of an acidic catalyst solution to the monomers.

Alternatively or desirably, papier maché may be mixed with binder or filler material and the papier maché, when set, provides further structural stability to the mat in addition 5 to altering the mat playing characteristics.

The amount of papier maché and/or the amount of binder can be varied to achieve the desired balance of structural support and playing characteristics. This can be done as a matter of 10 simple experimentation to achieve the desired results. For example, in packing material comprising papier mache and peaty loam, to increase the structural support provided by the packing material it is desirable to increase the proportion of papier mache relative to the peaty loam. To increase the 15 resilience of the packing material it is desirable to increase the proportion of peaty loam relative to the papier mache.

Preferably, the filler material and the mat are derived from a material(s) which is (are) biodegradable or have previously 20 been biodegraded and/or may be recycled for re-use as a filling material or other component of the present invention.

Conveniently, the mat is provided with an outer casing generally in the form of an open-top container with a base and 25 sides inside which is more or less tightly packed said

assembly of tubes packed with filler material. The container may be fabricated from plastic, metal, wood, cardboard or any combination of the foregoing. The base and/or sides may be provided with one or more holes to aid drainage therefrom.

5

The outer casing helps to maintain the structural integrity of the close packed tube assembly in use and during handling and facilities transport and/or storage of the mats. Preferably, the sides of the container are no deeper than the height of
10 the tubes of the surface playing material. Conveniently, the length of the sides of the container is somewhat less than the height of the tubes, e.g. 10 to 50% less.

The upper surface of the mat of the present invention can be
15 played off with or without placement of a golf tee. With a mat of the present invention, a golf tee can be placed anywhere on the upper surface by pushing the tee into the filler material within the honeycomb form support matrix. Where the support matrix is in the form of upright tubes or
20 the like, then the tee may also be inserted between adjacent tubes or into the filler material within the tubes as described.

Where the honeycomb form support matrix is a more or less
25 integrally-formed structure this is conveniently formed from a

first series of substantially parallel horizontally extending panels which intersect and optionally interlock at a predetermined angle with a second series of substantially parallel horizontally extending panels to form a plurality of
5 interstices between the intersecting first and second series of panels. The angle at which the first and second series of panels intersect can be from 15° to 90° relative to each series of panels. The interstices are packed with filler material and/or binder material and for any one or more of the
10 previously mentioned materials or substances according to the present invention. It will be appreciated that the filler material used in this form of the present invention may be as described as above with reference to the tube assembly form of the support matrix.

15

In another aspect of the present invention there is provided a practice support platform comprising a raised platform with a flat upper surface provided with a player standing area and at least one playing surface area, said at least one playing
20 surface area is provided with one or more recesses formed and arranged for receiving a mat according to the present invention. Preferably, the mat is provided within an outer casing according to the present invention. This has the advantage that the outer casing with the mat therein can be
25 placed into and can be taken out of the recess in the practice

platform with the minimum of effort. This provides quick, clean and efficient method of changing the mat whenever required.

5 The player standing area is typically a rectangular area adjacent the at least one playing surface area. Where two playing surface areas provided, it preferable that the player standing area is located there between such that the upper surface of the platform is divided into three areas.

10

When the playing surface of the mat becomes too abraded through use, the mat can simply be replaced or alternatively turned upside down and play continued on the other side of the mat where both sides of the support matrix are open. Where

15 only very localised damage has been sustained it may be preferable to remove and replace only those tubes which have been damaged in the case of a tube assembly form support matrix. This can be done by simply cutting out the damaged tubes (if the tubes are bonded to adjacent tubes) and

20 inserting replacement tubes. Water may be added to the replacement tubes after they have been correctly positioned. Where water-swellable filler material is used this helps to ensure that the tubes expand and pack tight against the surrounding tubes and/or the outer casing where present.

25

In a yet further aspect of the present invention, where the mat becomes abraded or worn through use or otherwise, a top layer of the mat may be shaved off to present a fresh playing surface. Where an outer casing is used, this may

5 conveniently be provided with a vertically movable base portion which can be used to raise the mat to bring the new playing surface thereof up to or above the sides of the casing. The casing may be provided with a base displacement means such as a jack.

10

When it is desired to shave off the top layer of the mat the movable base is moved upwardly by the displacement means such that the top layer of the mat is raised and a suitable cutting means may be used to remove the top layer thus leaving a fresh

15 clean, flat and undamaged playing surface.

To fabricate the mats of the present invention with a tube-assembly form support matrix it is envisaged that there may be used machinery formed and arranged for filling essentially
20 continuous tubes with filler material, which continuous filled tubes are then cut into tubes of the desired length(s). The cut filled tubes can then be assembled together into a mat with a bonding step where the cut filled tubes are glued or otherwise attached to adjacent tubes and/or with packing of
25 the cut filled tubes into an outer casing or other container.

The mat of the present invention can also in a further embodiment contain one or more colouring agents such as a dyestuff and/or a pigment. Preferably, the mat is coloured green by use of the appropriate colouring agents.

5

Further embodiments of the present invention can be envisaged where the mat of the present invention can be used for other sports such as soccer, American football, rugby, tennis, athletics, hockey and the like where the playing

10 characteristics required of the mat differ according to the particular sport. For example in sports such as rugby and American football the mat requires to be robust enough to withstand the relative high pressures and shear forces applied to the pitches at the points of scrimmage. Whereas for soccer
15 pitches and athletics tracks, for example, the mat requires to be relatively more resilient in order that it does not, in use, become too difficult to run and play on.

It is also envisaged that the mat of the present invention can
20 be used to replace areas of heavy wear such as those which frequently occur around the goal-mouths of soccer pitches and the base-line service points on grass tennis courts.

It will be appreciated that it will generally be possible and
25 in many instances particularly desirable, to mix grass seed

with the packing material located at or near the upper surface of the mat of the present invention. The mat may then be stored in a suitably dry condition to prevent germination and growth of the grass seed until such times as it is desired to
5 grow the grass.

Additionally or alternatively, the grass seed may be grown by the adding water to the mat and allowing the grass to grow thereon. The growth of grass provides a more natural surface
10 appearance to the mat, and additionally, the grass roots provide additional structural integrity to the mat as a result of inter-locking of the root systems between grasses growing in neighbouring tubes.

15 Where grass seed is provided in the present invention, it would be desirable to include a suitable fertiliser to aid the growth and/or condition of the subsequently grown grass. For example, the fertiliser may be added as a solid or liquid to the packing material.

20

Further preferred features and advantages of the present invention will appear from the following detailed description given by way of example of some embodiments illustrated with reference to the accompanying drawings in which: -

Fig. 1 shows a container containing a mat according to one aspect of that present invention;

Fig. 2 shows a support platform according to another aspect of the present invention;

5 Fig. 3 shows a paper tube packed with filler material for use in forming a mat according to the present invention; and

Fig. 4 shows a close up plan view of the mat according to one aspect of the present invention and the possible locations for placement of a golf tee thereon.

10

A mat, as generally indicated by the reference numeral 1, according to the present invention is shown in Fig. 1. The mat 1 is constructed from a large number of close packed upright paper tubes 2, which are glued together along mutually
15 co-operating edges. The tubes are approximately 10 cm in height with a diameter of approximately 2.5 cm. The tubes 2 are packed with a filler material 4 (see Fig. 3).

The mat 1 is contained in a rectangular container 6 with sides
20 8 which are approximately 1 cm less in height than that of the tubes 2. The container 6 is approximately 25 cm in length and 15 cm in width and the mat 1 is of substantially the same dimensions such that it fits tightly within the container 6.

25 A raised (approximately 20 cm from the floor to an upper

surface) rectangular support platform 10 (see Fig. 2) is provided with a player support area 12 located between two recesses 14. The player support area 12 is rectangular (75 cm x 60 cm) and is provided with a plastic non-slip surface 5 coating.

The recesses 14 on opposing sides of the player support area are rectangular (25 cm x 75 cm) and are formed and arranged to receive a plurality of containers 12. The recesses 14 have a 10 number of locating holes 16 which are formed and for receiving corresponding projections 18 extending from each of the corners of the base of the containers 14 where the containers 14 are placed in the recesses 14 as shown in Fig. 2.

15 A single tube 2 according to the present invention is shown in Fig. 3. The tube 2 is filled with packing material 4 which is sphagnum moss 20 intimately mixed with wood chips 22.

A plan view of the mat 1 of the present invention indicating 20 the hexagonal close packaging arrangement is shown in Fig. 4.

In the pulses hexagonal close packing arrangement each tube (or central tube) is typically surrounded by six other tubes forming a hexagon shape around the central tube. This is the case for every tube except those tubes 2 at the edge or corner 25 of the container 12.

Possible locations for placement of a golf tee (not shown) are indicated by the letters X Y and Z in Fig. 4, wherein : X is located on the top of a tube 2; Y is an interstice as defined by three neighbouring tubes in the hexagonal close packed formation; and Z is defined as the region between two neighbouring tubes. It will of course be appreciated that X, Y and Z are not intended to be limiting on the possible locations for placement of a golf tee and that the flexible nature of the mat 1 allows a golf tee to be placed substantially anywhere thereon.

Example

In one embodiment of the present invention, the tubes are formed from sheets of newspaper cut to the required size and rolled then taped (with adhesive tape) into the form of a cylinder with a diameter of about 12 to 16 mm and a height of about 12 cm. The tubes were packed (by hand) with commercially available peat moss (the composition of which is given below). A number of the thus formed tubes were close packed upright into an open top container with sides of length and breadth of 20 cm by 15 cm and a depth of 12 cm.

The composition of the packing material was determined as follows: The packing material (100 g) was heated in a domestic oven at 40 °C for 12 hours after which time the weight of dry

material recovered was 47 g; which is equivalent to the packing material comprising 53 wt% water and 47 wt% dry material.

5 The recovered dry material (47 g) was then roasted in air on an open metal plate heated by a Bunsen burner for approximately 45 minutes to remove the organic matter thereof. The material recovered after roasting weighed 18 g, and was designated as being mainly inorganic material. The dry
10 material was therefore determined to comprise: 62 wt% organic material and 38 wt% inorganic material.

The density of the uncompressed packing material as originally obtained commercially was determined by placing 100 g of the
15 packing material into a volumetric measuring cylinder which was firmly tapped around its outer surfaces to ensure the packing material was properly settled in the measuring cylinder. The volume occupied by the packing material was read off from the measuring cylinder. The density was simply
20 calculated thereafter as grams of material per cm^3 occupied by the material.

The density of packing material before drying was 0.52 gcm^{-3} (100 cm^3 packing material has a volume of 192 cm^3); the density
25 of the dried (at 40°C) packing material was 0.625 gcm^{-3} (100 g

dried material had a volume of 160 cm³); the density of the inorganic (roasted) material is 2.50 gcm⁻³ (100 g of the roasted material had a volume of 40 cm³).

5 The large volume of dried material is due mainly to the presence of relatively large particles of soil with correspondingly large air spaces therebetween. The dry material (and the moist packing material) had relatively large air spaces between the material particles, which in turn is
10 representative of a well aerated soil, which is particularly suited to use as a golf teeing off surface due to the inherent resilience provided by the material.

The particle size of the dry material was determined by
15 passing a known weight of the dry material through a series of sieves with known mesh sizes. The particle size distribution (as wt%) of the dry material was:

9-2 mm = 47 wt%; 2-1 mm = 21 wt%; ≥ 5 mm = 6.0 wt%; < 5 mm =
26 wt%.

20

Various modifications may be made to the above described embodiments without departing from the scope of the present invention.

action of the mats the system of tubes could be modified
 section forming a matrix, which is fitted into a frame or
 board , wood, plastic, metal or any combination of these
 and or any other suitable material. The outer tubes of the
 attached to the wall of the box by stapling ,gluing ,stitching
 appropriate physical or mechanical means. The tubes may or
 attached to the base of the container as required. This method of
 attaching the matrix of tubes to the wall of the container
 means of the tubes patent to facilitate the filling of the

forming the matrix can vary in diameter and length and the
 the material from which they are formed as can the type of
 paper ,plastic ,woven fabrics or any other suitable material.
 For the construction of different mats varying in size ,
 configuration specific for the purpose of its function.

mats may have holes or perforations in their walls at a diameter
 of spacing to facilitate even, lateral distribution of
 material and in those mats sown with grass seed to allow for
 growth of roots between the tubes to strengthen and bind the mat
 the grass turf produced on germination and growth is securely
 mat structure.

The frame ,box or container may be lined on the outer surface,inner surface or both surfaces as required.The lining material could be plastic, sheets of plastic , woven material of natural and or man made fibres. The lining could be porous or non-porous to water.

The walls ,the base or both may be perforated with holes the size and frequency of distribution may vary to allow drainage of water in different conditions.

The sides and base of the box/ container could be strengthened with strips or ribs of corrugated cardboard ,plastic ,wood ,metal or any other suitable material to facilitate its structural integrity in use ,handling, and storage.These strengthening ribs could be attached to the structure of the box or in pockets in any lining, if so used.

It is envisaged that one method of producing the mat is to place the empty box with matrix attached on a conveyer which will pass under a storage hopper which will dispense known volume of dry filler material on to the boxes upper surface. This volume of filler will over fill the tubes and lie on the upper surface of the tubes and mat to a known thickness required for the desired compactness and depth of the tubing. The tray or box will be vibrated to ensure the uniform filling of the tubes. The remaining known layer not entering the tubes by vibration will be compacted into the tubes by mechanical tamping or rolling this layer.

By experiment the pressure exerted by tamping or rolling will vary according to the density or compactness required in the tubing. The excess filler material will be brushed off the mat, for re-use. The filler material will conform to the specification required for the purpose and use of the mat. The mats will be wrapped, packed and stored.

The size of mat both in depth and surface area can vary. Surface area from 0.1 square metres or less to 2 square metres or more. Depth of mat from 2 centimetres or less 40 centimetres or more, as required for their purpose.

It is envisaged that in mats constructed on which grass seed is sown, for the growth of turf, the walls comprising the sides of the container could be 2 centimetres higher than the tubes comprising the matrix to form a lip and container for the seedbed in which the grass will grow.

It is envisaged that the dry filler material dispensed via the storage hopper could be replaced with a semi-dry soil/papier mache mixture. The method of construction would be the same as previously described. However, the mats once constructed would pass by conveyor belt through a continuous oven to remove moisture prior to wrapping and packing. The use of papier mache in the construction of the mat gives the advantage of greater cohesion and binding of the soil particles therefore providing added strength and durability of the mat.

It is envisaged that the papier mache to be used is provided by mechanically mixing in the ratio 20gram of newsprint with 1 litre of water. The temperature of the water can vary from 0 degrees centigrade to 100 degrees centigrade. The paper can be used as large sheets of newsprint or shredded newsprint. The newsprint can be new or recycled. The ratio of the dry weight of newsprint to water can vary. Decreasing the weight of newsprint or increasing the volume of water and thorough mixing gives papier mache or finer fibre separation but has less cohesive and adhesive properties. The converse is true.

Typically the material used in the composition of mats is in the ration of volume of 5 litre of papier mache to 5 litre of soil component. The papier mache and soil is thoroughly mixed and the excess water strained out by compression through a fine metal sieve. The soil content mixed with the papier mache can vary from inorganic sand and clay to organic composts and peat. The percentage proportions of each can vary from 100% to nil, according to the properties required of the mat for the type of club and golf shot to be practiced.

In some cases various plastics can be mixed with the papier mache such as polystyrene in the form of spheres of various sizes and shapes to form a material which exhibits similar properties to papier mache/soil mat.

The papier mache can be replaced by a system of natural fibres, wool, hair, plant fibre or man made fibres of plastic or any other suitable fibre, and natural glues or adhesives and manufactured glues and adhesives to form a mixture to replace the papier mache mixture.

The papier mache mixture can be used by mixing with the above described mixtures in varying proportions.

A mat can be produced without using a matrix of tubes using a papier mache and soil mixture. These mats do not exhibit the strength or durability of the mats containing the matrix of tubing but have the advantage being for the use by an individual golfer and being of a disposable nature.

It is envisaged that one method of production would be to mix the papier mache and soil as described, remove the excess water by mechanical straining and compression, remix the resultant mixture and place in cardboard or papier mache boxes of the dimensions of 30cm square and 4cm square depth. The mixture is tamped and rolled and then passed through continuous dry ovens to remove moisture then wrapped, packed and stored. It is also envisaged that the mats could be produced by mixing the soil and papier mache, straining removing excess water, remixing then extruding this dryer mixture through a dye to give a continuous sheet of 30cm width by 4cm depth. The dimension can be altered to give

mats of different sizes as required.

The extruded continuous mat is rolled to give uniform thickness and passed through a continuous dry oven. The matting can be cut into the required length either prior to or after drying. A plastic or cardboard edging can be wrapped around the side for added protection and strength in handling, package and storage. The dry mats are wrapped, packed and stored.

It is envisaged that a method of production for the papier mache soil mats would be by vacuum forming over a form or template. This can be done to form discrete mats of various sizes but typically of width 30cm length 30cm depth 4cm. The mats would be rolled to give uniform thickness and passed through by conveyor in a continuous drying oven. Vacuum forming could also produce a continuous roll of matting which could be cut into discrete mats prior to or after drying the mixture content. The moisture content, after drying, of the mats can vary from virtually nil, for storage, to a moisture content allowing immediate use. Dry mats would be re-hydrated with a known quantity of water prior to their use.

A mat of low adhesive properties of their component parts can be produced by mixing organic compost or peat with a high plant fibre content with known quantity of water, mixing thoroughly and forming into mat as

described in production method for the papier mache mats described on pages 28 and 29.

A mat consisting of only papier mache can be formed. The compactness of this can be varied by the pressure exerted by rolling or the vacuum force used in its production. High pressure producing a compact mat with few air spaces between the fibres. Low pressure less compact softer mat with many more airspaces between the papier mache fibres. The mats would be formed by production method for papier mache mats as described on pages 28 and 29 ,or by any other suitable means.

It is envisaged that the papier mache soil mixture can be utilised to form a mat without using a matrix of tubes. It does not have the integral strength and durability of a mat formed with the matrix of tubes but could be utilised to form a mat with a limited lifespan and of a more disposable nature. This allows the production of mats with different soil consistencies which allow the practice with wide range of golf clubs and golf shots ,especially the more lofted clubs which can take large divots and may cause substantial damage to the mat with less experienced golfers. However ,this would not cause a problem as the mat could be purchased and used by a individual golfer.

CLAIM 1

A rectangular mat for the practice of golfshots on which the the golf ball can be played from the surface of the mat or from a golf tee placed into the mat / and or a mat on which the surface is used to germinate and grow grass seed to produce flexible turf mats to replace worn or damaged existing turf on sports or recreational areas. The mats are constructed from a soil component which bound together and stablised by placing into vertical ajoining system of tubes which are glued together and by / or the addition of binders into the soil component such as plastic polymers ,papier mache natural plant fibres. The whole system is contained within a frame or box.

To.

GEOFF SHADBOLT

DEPARTMENT PDD/B. URGENT

FROM.

JOHN. G. BURNS.

FAX 01771 613429

02. JUNE. 2000.

NO. PAGES 2.

REF. PCT APPLICATION J.G. BURNS.

DEAR MR. SHADBOLT.

PLEASE SEE ATTACHED CLAIM. COULD YOU PLEASE
CONFIRM O.K. OR HOW TO AMEND.

THANKS.

J. G. Burns

CLAIM. 1.

A. RECTANGULAR MAT. FOR THE PRACTICE OF GOLF.
 SHOTS ON WHICH THE GOLF BALL CAN BE PLAYED
 FROM THE SURFACE OF THE MAT OR FROM A GOLF
 TEE PLACED INTO THE MAT./AND OR A MAT ON WHICH
 THE SURFACE IS USED TO GERMINATE AND GROW GRASS.
 SEED TO PRODUCE FLEXIBLE TURF MATS. TO REPLACE

WORN OR DAMAGED EXISTING TURF ON
SPORTS OR RECREATIONAL AREAS. THE
MATS ARE CONSTRUCTED FROM A SOIL COMPONENT
WHICH BOUND TOGETHER AND STABILIZED BY PLACING
INTO VERTICAL JOINING SYSTEM OF TUBES WHICH
ARE GLUED TOGETHER AND BY /OR THE ADDITION
OF BINDERS INTO THE SOIL COMPONENT SUCH AS
PLASTIC POLYMERS, PAPER MACHE, NATURAL PLANT
FIBRES. THE WHOLE SYSTEM IS CONTAINED WITHIN
A FRAME OR BOX.

ABSTRACT

Playing Surface Substrate

A rectangular mat on which the surface is used for the germination and growth of grass seed to produce turf mat to replace worn or damaged grass sports/recreational surfaces and or a mat to be used as a surface from which to hit golf balls.




Fig. 1




Fig 2




Fig. 3




Fig. 4